

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 36 N.R. 5 W


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 and 32

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 5/19/61

WITNESSES TO CORNER.....



5" Balsam - S60W - 19 links

6" Cedar - S28E - 26½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement at midpoint on line between section corners, after determining the theoretical position for the NE corner of Section 31 which falls in lake. The NE corner of Section 31 was fixed at the calculated intersection of the north and east lines of Section 31 based on mean bearings.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Oetting* DATE May 24, 1961  
REGISTERED LAND SURVEYOR