

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 5W


Emmet COUNTY

DESCRIPTION OF CORNER Meander corner common to Sections 30 and 31 on West side of

CORNER MONUMENT 1" pipe with 4" brass cap. Wycamp Lake.

DATE MONUMENT PLACED AND WITNESSED May 19, 1961

WITNESSES TO CORNER.....



5" B. Ash S42E 30. links

5" B. Ash N26W 24 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Set corner on margin of lake on calculated section line based on a mean bearing between north line of Section 30 and South line of Section 31. Unable to locate government BTs.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE May 23, 1961