

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 5 W

Emmet


COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 30-31

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 5/19/61

WITNESSES TO CORNER.....



7" Cedar ↗ S45E - 22½ links

5" Cedar - S65W - 27½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Set corner by single proportionate measurement, after determining the theoretical location of the NE corner of Section 31 which falls in lake. The NE corner of Section 31 was fixed at the calculated intersection of the north and east lines of Section 31, said lines being based on mean bearings between section lines 1 mile each way therefrom.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE May 23, 1961
REGISTERED LAND SURVEYOR