

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 5 W


Emmet COUNTY

DESCRIPTION OF CORNER Meander Corner common to Sections 19-30 on east side
Wycamp Lake

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 18, 1961

WITNESSES TO CORNER.....



6" W. Birch - N35E - 95½ links

6" Ash - S68E - 77 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of this township. Set corner on calculated true line between section corner east and meander corner on west side of lake, at margin of lake. Unable to identify government BTs.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 5/24/61