

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 5W


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, 33.

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED May 18, 1961

WITNESSES TO CORNER..... 5" Cedar - S53 $\frac{1}{2}$ W - 8 $\frac{1}{2}$ links



5" Cedar - N22E - 16 links

5" Cedar - S 6E - 20 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Set this corner to conform to apparent subdivision of Section 28. Placed corner on line and equidistant over what were considered acceptable locations for 1/4 and section corners north. This position checks exactly for measurement to 1/4 line fence and section corner east, and falls very near centerline of road in East 1/2 mile between sections 28 and 33. Could not consider double proportionate measurement for restoration of this corner because of gross discrepancies in government survey. This location appears most in conformity with apparent occupation in Sections 28 and 33.

SURVEYOR'S SEAL

SIGNED

Herbert J. Ostling
REGISTERED LAND SURVEYOR

DATE May 23, 1961