

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 38 N. R. 5W


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to sections 32 and 33.

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 18, 1961

WITNESSES TO CORNER.....



8" Cedar - S39W - 49 links

10" Cedar - S42E - 66 1/2 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Restored by proportionate measurement, midpoint on line between section corners, by Forestry Division survey crew while making a survey in this area. Unable to identify government BTS, but this point checks cutting lines and appears conformable to subdivision of section 33.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE May 23, 1961