

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 5W


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to sections 17,18, 19, and 20

CORNER MONUMENT 1" pipe with 4" brass cap, below surface

DATE MONUMENT PLACED AND WITNESSED May 18, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

24" Beech - S19W - 57 links

Fence corner - north - 49 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Restored by Forestry Division survey crew while making a survey in this area. Set corner in line with fence line north for longitude, at a point midway between E-W fence lines for latitude. Found large stone and pieces of broken crockery when setting corner, which falls about 4' south of apparent centerline of E-W county road. Checks good for measurement to section corner on townline 1 mile west. Considered best available evidence of proper location for corner.

SURVEYOR'S SEAL

SIGNED

Leitch Ostling
REGISTERED LAND SURVEYOR

DATE May 23, 1961