

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 38 N.R. 5"


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to sections 20, 21, 28, and 29.

CORNER MONUMENT 1" pipe with 1/4" brass cap, below surface.

DATE MONUMENT PLACED AND WITNESSED April 28, 1961

WITNESSES TO CORNER..... 5" Elm - S63W - 76 links



5" H. Maple - N27W - 108 links

Fence corner - East - 53 links

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established at apparent centerline intersection of roads N - S and W and in line with fence east. Checks midway between N-S fence lines and was considered best available evidence. Section 21 appears to have been subdivided on basis of this position.

**SURVEYOR'S SEAL**

SIGNED

*Kenneth J. Oething*  
REGISTERED LAND SURVEYOR

DATE May 25, 1961