

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 5 W


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 32 and 33 on south boundary of township.

CORNER MONUMENT Drove 1" pipe through blacktop

DATE MONUMENT PLACED AND WITNESSED April 28, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Cedar - N40W - 61.2 feet

5" Cedar - N28E - 46.1 feet

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measurement between corners 1 mile east and 1 mile west. Could locate no previous corner, OBTs gone. Falls about 7' south of present centerline of blacktop, but very nearly midway between fences for latitude.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 5/24/61