

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

LIBER 2
PAGE 1+1

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>38</u> N. _____ R. <u>05</u> W. _____		<u>F-3 N 1/4 Cor. SEC. 9</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

STATE OF MICHIGAN
EMMET COUNTY
Recorded Oct 18, 1985
At 3:40 Clock PM
Carl F. Roser
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCTOBER 15, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

F-3 (N 1/4 COR, SEC 9)

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (JOHN MULLETT) 1840 "WEST CORRECTED BETW SEC'S 4 & 9, 39.89 (ch's) BEECH 8 QR SECTION CORNER.

M. PALMER, CO. SURVEYOR, APRIL 1902, SURVEY & SEC SUB'N OF SEC 9, T38N-R5W, AT N 1/4 COR. SEC 9, "CEDAR POST 4, POPPLE 5 NORTH 6.3', W. BIRCH WEST 16.2": ESTAB MIDWAY & ON LINE BETWEEN FD GOV. COR. AT NE & NW SEC 9. NOTES ON FILE AT EMMET CO. REG OF DEEDS, PG 18 OF LARGE BROWN CO SURVEYORS LIBER.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
FOUND VERTICAL POST BOTTOM WHILE SCALPING AT PALMER POSITION AND CEDAR POST REMAINS LYING HORIZ. POST BOTTOM WAS RECOVERED ON OCT 9, 1985 BY R. O'HARA, JOHN SWANSON, HAROLD KIBBE DURING RETRACEMENT OF M. PALMER 1902 SEC. 9 SURVEY. VERIFIED AND PHOTOGRAPHS TAKEN OF OLD POST BOTTOM BY C. ROSER ON 10-15-85.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
FOUND OLD POST BOTTOM (VERTICAL) THAT FITS M. PALMER 1902 SURVEY OF SEC. 9. SET STD DEPT MON (4" ALUM DISK ON 1" x 36" PIPE) & CEDAR POST W/LOC TAG.

15" RED PINE	N22°W	17.0'
14" RED PINE	N54°E	36.0'
17" WHITE PINE	S63°E	9.2'
11" WHITE PINE	S15°W	25.3'

E-W (WINDING) TRAIL IS 127'± SOUTH.

SIGNED BY Carl F. Roser 10-18-85 DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. L.S., P.E., 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET T38N-R5W EMMET COUNTY