

Note: Original sheet in field notes
for T38N-R5W, Proj # 31-93240
This Cor. Already Typed & recorded & filed

(2)

Do Not Type	CTR & R.O. #1	10-15-85	(43B)
At N ¹ / ₄ Cor. Sec. 9, T38N-R5W Emmet Co. to take 2- Polaroid Picture (& one River Minolta Kodacolor ^{#3}) of Fd. vertical post bottom & Ced. Post remains lying horizontal. Note post bottom was recovered on Oct. 9, 1985 by Robt. O'Hara, John Swanson & Harold Kibbe. in pit (w hump in middle) from ^{disg.} _{corner}			
Set Std. Dept Mon (Alumin. disk on 1" x 36" Pipe at ^{post #4} ₁₀₋₁₅₋₈₅ Fd. Post Bottom.			
15" R. Pine		N 22° W	17.0'
14" R. Pine		N 54° E	36.0
17" W. Pine		S 63° E	9.2'
11" W. Pine		S 15° W	25.3'
E-W (winding) trail is 127± South			

DIETZEN NO. 284-B