

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

LIBER 2
PAGE 142

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>38</u> N. <u>5</u> W.	G-3 <u>NE COR</u> <u>SEC 9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

STATE OF MICHIGAN
EMMET COUNTY
Recorded Oct 15, 1985
At 3:45 O'Clock P.
Carl F. Roser
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCTOBER 15, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


G-3(NE COR SEC 9)
A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. (JOHN MULLETT) 1840
SET POST CORNER SEC'S 3,4,9,10 - HEMLOCK 12 N45E 26
BEECH 9 N19W 08

M. PALMER, CO. SURVEYOR, NE COR OF SEC 9, T38N-R5W, APRIL 1902, PG 18 OF LARGE CO. SURVEYOR'S LIBER AT EMMET CO. REG OF DEEDS "FOUND GOV. COR., SET CEDAR POST 6"

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
R. O'HARA, JOHN SWANSON, HAROLD KIBBE FOUND CEDAR POST BOTTOM, VERTICAL, (6" ROTTED) WHILE SCALPING FOR COR FROM SURVEY DATA FROM RETRACEMENT OF M. PALMER'S 1902 SURVEY OF SEC 9; OCT 9, 1985. O'HARA SHOWED THIS CORNER TO C. ROSER ON OCT 15, 1985 WHO VERIFIED THIS AS RECOVERING M. PALMER'S CEDAR POST, PALMER HAVING THE ORIG 1840 G.L.O. COR. ROSER TOOK PHOTOGRAPHS OF THE RECOVERED CEDAR POST BOTTOM IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
6"x24" (below ground)
FD. CED. POST BOTTOM (PALMER 1902). LEANED POST BOTTOM WEST AND DROVE 5/8" x 35" REROD W/PLASTIC RLS CAP #12028.

SET CED POST W/LOC TAG	WEST	33'
17" RED OAK	S83°W	50.51
OLD COR FN POST (irreg fn remains S'ly & W'ly)	N25°W	103.64
23" RED OAK	N74°E	50.25
15" RED OAK	S51°E	58.14
FD 3/4" ROD	N05°50'E	93.78
CTR N-S GRAVEL RD (LOOKING SO.)	EAST	3'+
CTR GRAVEL RD IN CURVE	EAST	16'+



SIGNED BY Carl F. Roser 10-18-85 DATE _____
SURVEYOR'S MICHIGAN REGISTRATION NO. L.S., P.E. #12028 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SKETCH ON BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET T38N-R5W EMMET COUNTY