

10-15-85	C772 & R. O'H	Back of 43A
N.B. Ts to fd. 6" Ced. Post		
Bottom per M. Palmer (1902)		
who had Orig. Govt. Cor. here		
Drove 5/8" x 35" rod w/ plastic old Cd		
RLS Cap # 12028 - D. N.R. Larneg. 1st Post West		
17" R. Oak	S83°W	50.51
Cor. 70. Post fr. W. by S. 1/4	N25°W	103.64
23" R. Oak (Turn oak above) 6" high	N74°E	50.25
15" R. Oak	S51°E	58.14
Set Sq. Top Ced Post w/ loc. TAG	West	33'
Ctr. of N-S gravel Rd, Looking south	Due E.	3' ±
Ctr gravel Rd. in curve	Due E.	16' ±

Note: Original sheet in field notes  
for T38N-R5W pr. #3193290

This Cor already typed & Recorded  
& filed Bob O'Hara & Carl Roser 10-15-85

No No  
Type

At NE Cor. of Sec. 9, T38N-R5W,  
Emmet Co. to take 3 - Polaroid  
Color Pictures and 2 - Kodacolor

prints (on Roser's Minolta) of  
recovered 6" post bottom remains  
as noted in old Co. Surveyor's  
notes on record at Emmet Co.

Reg. of Deeds (Pg. 18 of Large Brown  
Co. Surveyors Liber) dated 19 Apr.,  
1902, M. Palmer Co. Surveyor.

Note: This Cedar Post (Post Bottom)  
was found while searching for  
corner by Robt. O'Hara, John  
Swanson & Harold Kibbe on

Oct. 9, 1985.

This Palmer's Corner (Set 6" Ced. Post)  
from "found Gov. Corner"

Took N.B. T.'s - Sec back of  
this page - C7R & R. O'H.