

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ENNET
 (County)

Located In: Corner Code ~~≠~~

1. Public Land Survey	T <u>38N</u> R <u>5W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>1</u> T _____ R _____	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S <u>1</u> T _____ R _____	<u>11915' W OF L-2</u>
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, CARL F. ROSER, in a field survey on JULY 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 (NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)	K-1 CONTINUED ABOVE GRD) AS FD (& ACCEPTED) BY RLS JOHN FERGUSON FOR NW COR S-1; THIS IS NOT THE NW OF S-1 AS SOLL FD GLO NW S-1 AS NOTED ABOVE. THE ORIGIN OF THIS BOGUS NW S-1 MUST BE THE POINT AS NOTED, TIED AND SHOWN ON SOLL SUR MAP AS FD 5" SOD CED POST, S7°05'W, 56.8' (WE GET S06°40'W, 56.78'). FOR MORE BACKGROUND ON SOLL SUR SEE NE COR S-1 (M-1).	8 ("B" CONTINUED): NE FD 1/2" REROD, LEANING NE, 3' ABOVE GRD ON E SIDE OF 14" POPLAR, WHICH IS J.FERGUSON'S. 1/8 COR. CORNER OF OLD FM (FM'S E & S) IS 13'± S AND 12'± E. CTR OF N-S DIRT RD IS 18'± W.	1 ("B" CONTINUED): E'LY EDGE OF WILLOW AND ALDER SWP IS 30' (± 10') WEST. E'LY EDGE OF WATER (MUD LK) IS 200'± (ROUGHLY) WEST.
--	--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 FD 1 1/2" PIPE AS SET BY RLS FRED SOLL AT POSITION OF FD PINE STK POINT THAT FIT ALL (4) US B.T.'S (STUMPS); COR COMM TO SEC'S 35 & 36 (39N-5W) & SEC'S 1 & 2 (38N-RW), CLOSING COR EQUALS STD COR. SOLL MADE COMPLETE RETRACEMENT SUR OF T39N-R5W, SUMMER 1928. E-W TRAIL ON SMALL E-W RIDGE IS 10' ± N. TRAIL NE IS 65'± E. FD OLD RUSTY 1" PIPE (9"	K-1 CONTINUED ABOVE GRD) AS FD (& ACCEPTED) BY RLS JOHN FERGUSON FOR NW COR S-1; THIS IS NOT THE NW OF S-1 AS SOLL FD GLO NW S-1 AS NOTED ABOVE. THE ORIGIN OF THIS BOGUS NW S-1 MUST BE THE POINT AS NOTED, TIED AND SHOWN ON SOLL SUR MAP AS FD 5" SOD CED POST, S7°05'W, 56.8' (WE GET S06°40'W, 56.78'). FOR MORE BACKGROUND ON SOLL SUR SEE NE COR S-1 (M-1).	8 ESTAB SE COR OF SW 1/4 OF NW 1/4 OF S-1, MIDWAY & ON LINE BETW N 1/4 COR S-1 (CALC POINT IN LAKE) AND CTR OF S-1 (INTERSECT OF ONE-QUARTER LINES- THIS, DNR, SUR). THE NW COR OF PARCEL "A" OF CERTIFIED SURVEY BY RLS JOHN FERGUSON, DATED JAN.25,1980, IS S05°16'23"W, 21.11'. (CONTINUED IN "A")	1 ESTAB MEANDER CORNER ON E-W 1/4 LINE OF S-1 AND NEAR E'LY SWP EDGE OF LAWRENCE (MUD) LAKE. W 1/8 COR ON E-W 1/4 LINE IS N88°21'35E, 602.31' AND CTR OF S-1 (THIS, DNR, SUR) IS N88°21'35E, 1915.10'. THE N.C. ON N LINE PARCEL "P" OF RLS J. FERGUSON CERT SUR, DATED JAN 25, 1980 IS SOUTH 33.12'. (CONTINUED IN "A")
--	--	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 FD 1 1/2" X 49" PIPE THRU 5 GAL GALV PAIL & STONES; ADDED CED POST W/LOC TAG. 822° W PINE N89°E 95.2' 816° NORWAY PINE S70°E 62.3' 816° NORWAY PINE S54°E 63.4' 812° NORWAY PINE S 3°E 57.0' 818° WHITE PINE S57°W 79.5' 814° NORWAY PINE S85°W 75.9'	K-1 CONTINUED 832° WHITE PINE N21°W 34.8' 8F. SOLL 1928 WITS.	8 DROVE 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG. 14" BEECH N10°W 18.6' 8" SUG MAPLE N70°E 6.2' 3" BEECH S10°E 23.2' 10" W PINE N80°W 83.4'	1 DROVE 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG. 11" CEDAR N45°W 11.7' 7" CEDAR N10°W 8.7' 8" CEDAR S60°E 15.7' 9" CEDAR S50°W 6.9'
---	--	--	---

Signed by Carl F. Roser 12-09-93 Date _____
 Surveyor's Michigan License No. 12028

