

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>EMMET</u> (County)	Located In:	Corner Code <u>1-5</u>
1. Public Land Survey	T <u>38N</u> R <u>5W</u>	<u>H-5, 1-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>15</u> T _____ R _____	<u>1, 2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, C.F. ROSER, in a field survey on OCTOBER, 24, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREE'S OR TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. NOTES; UNLESS NOTED IN ITEM "B" BELOW)

I-5, B CONT. -- I BELIEVE WE HAVE RECOVERED THE SAME CORNER. COR ALSO APPEAR'S TO FIT CO. SURVEYOR, S.G. MAIN'S 1911 SURVEY OF SEC. 15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5	I-5	1	2
RESTORED NW1/4 COR OF SEC 15 FROM FD REMAINS OF ONE WIT, PER 1911 CO SURVEYOR, S.G. MAIN, SUR & SEC SUB'M OF SEC 15 (FD 17" SUB. MAPLE TIP OVER ON GROUND W/LOWER FACE). (REFERENCE: DNR SUR MAP OF SEC 3 & 10, T38N-R5W, AND SURVEY REPORT).	ACCEPTED FD IRON, CROCKERY & STONE'S FOR SE COR OF SEC 10. CORNER FALLS IN BIT. SURFACE CO RDIGILL RD). COR FALLS IN APPROX CTR OF TRAIL LOOKING N. CTR OF E-W BIT RD (IN SMALL CURVE) IS 3' S. COR IS IN APPROX. CTR OF GRAVEL RD LOOKING S. CO RD COMM WIT SHEET (1957) SAY'S "FD SEC COR WHICH APPEARS TO BE TWO PLOW SHARES ON END"; SEE ABOVE	ESTAB. NE CORNER OF NW1/4 OF NW1/4 OF SEC 15; PER STD B.L.M. INSTRUCTIONS FOR SEC SUBN'S. OLD E-W, W-W, FN IS 100'± SOUTH. (REFERENCE: DNR SURVEY MAP OF SEC'S 3 & 10, T38N-R5W, AND SURVEY REPORT).	ESTAB. NE COR OF W1/2 OF NE1/4 OF SEC 15; PER STD B.L.M. INSTRUCTIONS FOR SEC SUBN'S. OLD FN REMAINS S'LY (ON GROUND) ARE EAST, 23'±. CTR OF B.TOP RD IN CURVE, IS 7'± NORTH. (REFERENCE: DNR SUR MAP OF SEC 3 & 10, T38N-R5W, & SURVEY REPORT)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5	I-5	1	2
SET DNR MON AND CEDAR POST. 10" S. MAPLE N60°W 11.4' 16" BEECH N65°E 19.8' 12" S. MAPLE SOUTH 18.8' 8" S. MAPLE S30°W 5.2'	FD 2 PIECES OF CAST IRON 23" LONG x 4" x 3/4" AVERAGE THICKNESS. ADDED 5/8" x 34" REROD W/LS CAP. 28" S. MAPLE N25°W 76.03' 4" S. MAPLE N15°E 75.97' 9" S. MAPLE N30°E 41.60' 12" S. MAPLE S15°W 114.67' SET CEDAR POST W/LOC TAG DUE NORTH 33'	DROVE 5/8" x 34" REROD W/LS CAP & SET CEDAR POST W/LOC TAG. 2" ASH N40°W 39.4' 3" MAPLE S10°W 65.5' 2" MAPLE S60°W 28.5' 2" IR. WOOD S05°E 62.4'	DROVE 5/8" x 17" REROD W/LS CAP. 10" BEECH S30°E 35.4' 11" S. MAPLE S10°E 34.7' 4" S. MAPLE S25°W 35.6' SET CEDAR POST W/LOCATION TAG SOUTH 33'

Signed by Carl F. Roser 4-16-93 Date _____
 Surveyor's Michigan License No. 12028

