

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ENMET

(County)

Located In:

Corner Code =#

- | | | | | | |
|------------------------------------|---|------------|---|-----------|-----------------|
| 1. Public Land Survey | T | <u>38N</u> | R | <u>5W</u> | <u>J-5, K-5</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | <u>11</u> | T | _____ | <u>14</u> |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, C.F. ROSE, in a field survey on MAY, 14, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (NO EVIDENCE OF G.L.O. CORNERS, B.T.'S, LINE TREE'S OR TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS OTHERWISE NOTED IN ITEM "B" BELOW)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5	K-5	14
FD IRON IN CTR OF E-W B.TOP RD FOR S1/4 COR OF SEC 11. CORNER BELIEVED TO BE BY LS, J.H.BREEN & FITS OUR CALC SP 1/4 COR POSITION WITHIN 0.3'±; ACCEPTED FD IRON.	FD 3/4" ROUND IRON FOR SE COR OF SEC 11; NO EVIDENCE OF RD COMM W/TS. CTR OF GRAVEL RD (NNE) IS 13'± E. COR IS IN APPROX CTR OF E-W BIT SURFACE RD. COR IS IN LINE W/APPROX CTR OF BIT SURFACE RD TO SOUTH (LOOKING SOUTH 350').	ESTAB NE COR OF S1/2 OF SE1/4 OF SEC 11; PER STD B.L.M. INSTRUCTIONS FOR SEC SUBN'S. CTR OF GRAVEL RD (NNE-SSW) IS 300'± EAST. OLD E-W FN REMAINS (ON GROUND) ARE 7'± SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5	K-5	14
FD IRON W/LS CAP.	FD 3/4" ROUND IRON.	DROVE 3/8"x 5/8" GALV PIPE W/LS CAP & SET CEDAR POST W.LOC TAG.
*POWER POLE N15°W 32.31'	3"W.PINE N50°W 56.8'	8°CEDAR(CLP) N55°W 23.8'
SE COR OF CONC BLK CABIN FOUNDATION N13°W 126.0'	3°CEDAR N42°E 71.4'	7°CEDAR N15°E 2.9'
14°TN.S.MAPLE S25°E 62.33'	POWER POLE S65°E 83.88'	21°TN.MAPLE S65°E 35.5'
*8°S.MAPLE S52°W 58.35'	12°CEDAR S60°W 112.2'	8°CEDAR S80°W 31.4'
SET CEDAR POST WITH LOC. TAG NORTH 33'	SET CEDAR POST WITH LOC. TAG NORTH 33'	

*± JHG. LS015401. NIT

Signed by Carl F. Roser 4-16-93 Date
 Surveyor's Michigan License No. 12028

