

MAR 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

1994 FEB 14 AM 10:15

For corners in

EMMET
(County)

Located in: CROSS VILLAGE TOWNSHIP
Corner Code #

38N 6W I-11

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Glenna B. Sizer
REGISTER OF DEEDS

LIBER A
PAGE 23

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is present in row 11, column I.

Richard E. Oelke 27 December 93

I, in a field survey on, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11, Section corner 26,27,34, & 35 T38N, R6W

- 1840 GLO 12" Birch
-1976 Bidstrup LCRC, Liber 1, page 228, fd. 3/4" iron pipe.
(1) N20°E, 41.44', 5" cedar
(2) S80°W, 30.77', 6" white pine
(3) N10°W, 6.12', 20" oak
-1978 L. Feindt Survey for Carey, fd 1" IP next to old square post broken off near ground level.
(4) N67°E, 5.17', 7" maple
(5) S45°W, 28.26', 4" maple
(6) N30°W, 38.71', 8" white pine
-1987 Green Plat of Childwood, Liber 9, page 37, shows corner as being inside Lot 7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11, Section corner 26,27,34, & 35 T38N, R6W

Found 1" iron pipe, 2' long, .3' below the surface. Also fd. remains of old post 3" diam. 1.5' long, .3' above surface and also fd. remains of second post 4" diam, 2.5' long, 1' below surface.

- N10°E, 41.29', fd (1), 6" cedar 40d in E face
N68°E, 5.15', fd (4), 6" maple tagged #16034 in S face
S78°E, 21.98', 14" oak tagged #16034 in S face
S43°W, 28.39', fd (5) 6" maple tagged #16034 in SE face
S55°W, 30.82', fd (2) 6" white pine 40d spike in SE face
N40°W, 6.12', fd (3) 20" oak 40d spike in SW face



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11, Section corner 26,27,34, & 35 T38N, R6W

At the position of the 1" iron pipe, set a 2" diam., 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful perpetuation of the position of the original corner.

- N10°E, 41.29', fd (1), 6" cedar 40d in E face
N68°E, 5.15', fd (4), 6" maple tagged #16034 in S face
S78°E, 21.98', 14" oak tagged #16034 in S face
S43°W, 28.39', fd (5) 6" maple tagged #16034 in SE face
S55°W, 30.82', fd (2) 6" white pine 40d spike in SE face
N54°W, 39.24', 16" red pine tagged 33983 in NE face
N40°W, 6.12', fd (3) 20" oak 40d spike in SW face

Signed by RICHARD E. OELKE Date 14 JANUARY 1994
Surveyor's Michigan License No. 33983