

APR 29 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

1995 DEC 19 PM 1:38

For corners in EMMET (County) Located In: Corner Code #

1. Public Land Survey EMMET COUNTY REMON. CORNER #99 COMMON TO SECTIONS 34 & 35	T _____ R _____ T _____ R _____ T <u>38 N</u> R <u>6 W</u> T _____ R _____	_____ <u>1-13</u> _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Glenna L. Sjies
REGISTER OF DEEDS

LIBER A
PAGE 91

Register of Deeds Stamp & File Number

I, Michael A. Trowbridge, in a field survey on DECEMBER 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
113....CORNER COMMON TO SECTIONS 34 & 35, T38N, R6W

SEE EMMET COUNTY REMONUMENTATION PROGRAM CHRONOLOGY OF GLO CORNER ON BACK SIDE OF THIS PAGE.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R. E. C. E. V. E.
21 DEC. 95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
113....FOUND 5/8" REROD WITH CAP 11350.

FOUND WITNESSES
5) S13'E 11.03' 2" MAPLE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

113....THE 5/8" REROD WAS REMOVED AND REPLACED WITH A 2" DIAMETER X 30" LONG PVC PIPE, A BASE MAGNET AND A STANDARD BRASS EMMET COUNTY REMONUMENTATION CAP. THIS POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

EAST 31.02' EMMET COUNTY REMONUMENTATION MONUMENT
AZIMUTH 230° 30.61' 8" MAPLE (SET 27463 CAP AND NAIL IN SOUTH FACE)
AZIMUTH 291° 15.86' 6" POPLAR (SET 27463 CAP AND NAIL IN NORTHEAST FACE)
AZIMUTH 344° 34.55' 8" TWIN MAPLE (SET 27463 CAP AND NAIL IN EAST FACE)



Signed by *Michael A. Trowbridge* Date 12/11/95
Surveyor's Michigan License No. 27463

EMMET COUNTY REMONUMENTATION PROGRAM

CHRONOLOGY OF GLO CORNER

REMON. CORNER #99 LCRC #38-06-113sc TOWNSHIP...CROSS VILLAGE
CORNER COMMON TO SECTIONS 34 & 35, T38N, R6W

DATE	SURVEYOR	FOUND/SET	WITNESSES
1840	GLO	SET POST	1) N33°E 90 LINKS 18" SUGAR 2) N35°W 90 LINKS 14" B. OAK
1977	BIDSTRUP	SET 5/8" ROD WITH CAP	3) N13°W 44.58' 4" OAK 4) S74°W 14.02' 12" OAK 5) S13°E 11.03' 2" MAPLE

SEE RECORDED SURVEY, LIBER 278, PAGE 852.

