

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 NR. 5 W.  
T 38 NR 6 W

Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19-30-24-25

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" R. Pine	-	S63W	-	93½ links
7" R. Pine	-	S4E	-	99 links
14" R. Pine	-	N7E	-	181½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in T38NR6W. Set corner from probable original BT stumps, NW stump showing evidence of face, pine stump SW, and hole at site of NE Oak. Checks very good for line and distance over 1/4 and section corner north. Found evidence of a very old fence coming in to this corner from south and west.

Corner was placed and witnessed April 22, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 4/25/60