

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 6 W


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25-26-35-36

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 27, 1961

WITNESSES TO CORNER.....



8" Aspen	-	N83W	-	28 links
30" W. Pine Stp	-	N38E	-	20½ links
AND 6" W. Birch	-	S23E	-	44 links

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Set corner by proportionate measurement for longitude between corners 1 mile east and 1 mile west, at record measurement south of swamp edge. This makes mile south about 80 links short but conforms fairly well with apparent protraction of Section 26. Also puts 5 chain error in Section 25 where it is identified on east line. Unable to identify original BTs. See section subdivision and minutes of survey of Section 25 for more information.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE

5/24/61