

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 6W


Emmet COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 23, 24, 25, and 26.

CORNER MONUMENT 1" pipe with 1/4" brass cap.

DATE MONUMENT PLACED AND WITNESSED April 6, 1961

WITNESSES TO CORNER.....



8" R. Oak - N61W - 22 links

8" R. Oak - S72E - 21 1/4 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew. Restored this corner on line, and equidistant over original 1/4 and section corners east. Corner falls on east slope of very large sand dune. Suspect that government BT stump may be covered. Cannot double proportion since no good meander corners are available north and west.

SURVEYOR'S SEAL

SIGNED

Ernest J. Ostling
REGISTERED LAND SURVEYOR

DATE May 25, 1961