

**SURVEY & REMONUMENTATION**

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

1994 DEC 28 AM 11:04

For corners in **COMMISSION**

**EMMET**  
(County)

Located In: **WAWATAM** Corner Code #

1. Public Land Survey	T	39N	R	4W	I-6
ECRP #79	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*Shenna C. Sipe*  
REGISTER OF DEEDS

LIBER A  
PAGE 69

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**Richard E. Oelke** 30 November 94

I, Richard E. Oelke, in a field survey on 30 November 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-6, 1/4 corner between sections 14 & 15, T39N, R4W
- 1840 GLO Set post S41°W, 051ks, 6" sugar;  
S37°E, 161ks, 6" ironwood
  - 1961 GE Young Survey #441, shows symbol at corner.
  - 1981 JE Young Survey for Deering, found T-iron. (LCRC 2/100)
    - (1) S50°E, 29.00', 6" basswood
    - (2) S54°W, 35.80', 15" oak
    - (3) N27°W, 58.90', 8" maple



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6, 1/4 corner between sections 14 & 15, T369, R4W

Found railroad spike .5' west of centerline of Headlands Road, 1' below ground found T-iron with bent top. Base of T-iron fit witnesses to SE & SW.

- (1) S50°E, 29.00', 6" basswood, tagged 24626 N face
- (2) S55°W, 35.80', 15" oak, tagged 24626 N face
- (3) N27°W, 58.62', 8" maple, tagged 24626 E face

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County

*R. E. Oelke*  
27 DEC 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6, 1/4 corner between sections 14 & 15, T39N, R4W

At the "T-iron", set a 2" diam., 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, 15" below the surface. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

Added following new accessories

- N90°E, 33.30', concrete monument, with 1/2" iron pipe
- S52°E, 43.18', 12" aspen, tagged 33983 S face
- S45°W, 51.30', 12" oak, tagged 33983 N face
- N80°W, 79.51', 12" cedar, tagged 33983 N face

Signed by R. E. Oelke Date 30 NOVEMBER 1994

Surveyor's Michigan License No. 33983