

SURVEY & REMONUMENTATION

APR 27 1995

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

1994 DEC 28 AM 11:04

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

EMMET
(County)

Located In: WAWATAM

Corner Code #

1. Public Land Survey
ECRP #80

39N 4W

I-7

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Alma C. Sizer

REGISTER OF DEEDS

LIBER A

PAGE 70

Register of Deeds Stamp & File Number

Richard E. Oelke 30 November 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7, Section corner between sections 14, 15, 22 & 23, T39N, R4W

-19?? ECRC Witness sheet shows found 1/2" iron pipe and 1-1/2" iron rod and placed monument box at iron pipe as it fit roads. Witnesses appear to have been taken at a later date.

- (1) N60°E, 30.45', 18" birch
- (2) S30°W, 13.80', state park sign
- (3) N40°W, 58.85', tele cable marker

-1958 J. Doyle Plat of Mery-Away-On-The Bay (05-33), symbol indicates found.

-1960 O. Doyle Plat of Mery1-Away-On-The-Bay First Addition (06-03), symbol indicates found.

-1981 JE Young Survey for Deering, found pipe. (LCRC 2/100)

- (4) N33°E, 68.50', 3" balsam
- (5) S48°E, 47.50', 5" cedar
- (6) S47°W, 45.20', state park sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7, Section corner between sections 14, 15, 22, & 23, T39N, R4W

Found 1/2" iron pipe, projecting .5' out of a concrete filled 3" iron pipe, 1.3' long, .6' below the surface in a monument box, at centerline intersection of Trails End Road and Headlands Road. I excavated approximately 2.5' to native limestone, no other evidence was found at this point. Found 1-1/4" square iron bar, 1' long, .4' below surface, 3' N. of centerline Trails End Road and 4' W. of centerline Headlands Road. I excavated a large hole to native fractured limestone and found no other evidence this point was not accepted as Section corner. (see section C for tie to iron bar)

- (4) N33°E, 68.55', 3" balsam, tagged 24626 SE face
- (5) S48°E, 47.51', 5" cedar, nail in NE face

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. OELKE
27 Dec. 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7, Section corner between sections 14, 15, 22 & 23, T39N, R4W

At the 1/2" iron pipe, set a 2" diam., 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, 15" below the surface. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

- Additional new accessories
- N45°E, 46.57', concrete monument, with 1/2" iron pipe
 - S44°W, 72.84', fd 1/2" iron rod capped #12581
 - S48°W, 78.05', 18" spruce, tagged 33983 SE face
 - N65°W, 4.58', fd 1-1/4" sq. iron bar, see section B above
 - N78°W, 142.98', 12" cedar, tagged 33983 S face



Signed by RICHARD E. OELKE Date 30 November 1994

Surveyor's Michigan License No. 33983