

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER Meander corner common to Sections 23 - 26 on west side of lake

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 8, 1964

WITNESSES TO CORNER.....



20" R. Pine N 64 W 70.4'

8" R. Pine N 1 W 83.0

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this township. Set corner on line between section corners at the west shore of French Farm Lake. Area all disturbed by filling, and used as access point, so all previous evidence destroyed.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE June 26, 1964
REGISTERED LAND SURVEYOR #19068