

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N. R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22 - 23 - 26 - 27

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 8, 1964

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

18" R. Pine N 17 E 35.6'

7" R. Oak N 70 W 27.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Believe we recovered the remains of an old charred cedar stake point while digging relative to probable U. S. BT's stumps. Both stumps in place, the SW with axe notch which could be part of lower face. Also fits very well to swamp edges one chain north and 1 1/2 chains west. Okay for bearing north and for distance to the lake east and south. Probably a restoration of the original corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE June 26, 1964
REGISTERED LAND SURVEYOR #10068