

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 22 - 27

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 8, 1964

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" Cedar S 85 W 12.6'

9" Cedar N 37 E 16.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this area. Set corner on line between Section corner east and M. C. west, at U. S. record measurement. Could locate nothing for previous corner or BTs.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE June 29, 1964
REGISTERED LAND SURVEYOR #10068