

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 39 N. R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER M. C. corner common to Sections 22 - 27 on Lake Michigan

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 8, 1964

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Cedar S 61 E 26.0'

8" W. Pine N 14 W 21.4'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this township. Set corner on prolongation of true line between 23 - 26 and at record measurement from section corner of 22 - 23 - 26 - 27. Nothing left for U. S. BT's, but falls about right for meander line location of 1840.

SURVEYOR'S SEAL

SIGNED *Kenneth Jostling* DATE June 8, 1964  
REGISTERED LAND SURVEYOR