

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 4 W.


EMMET COUNTY

DESCRIPTION OF CORNER 1/4 CORNER COMMON TO SECTIONS 30 - 31

CORNER MONUMENT SET 1" PIPE WITH 4" ALUMINUM CAP

DATE MONUMENT PLACED AND WITNESSED MAY 21, 1965

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8"	SPRUCE	N 3 E	11.3
6"	BALSAM	S 78 E	23.4

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS ESTABLISHED BY PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS. UNABLE TO LOCATE ANYTHING FOR U. S. T. BS. A SQUARED POST IS ABOUT 25 LINKS NORTH AND 12 LINKS EAST BUT DOES NOT TIE IN WITH SECTION CORNERS, NOR IS IT SUPPORTED BY U. S. EVIDENCE. APPARENTLY WAS SET WITH SOME KNOWLEDGE OF TOTAL LENGTH OF MILE WHICH IS LONG, BUT IT IS FELT A SINGLE PROPORTIONATE MEASUREMENT BEST RESTORES THE PROPER POSITION FOR CORNERS.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE JUNE 14, 1965
REGISTERED LAND SURVEYOR #10068