

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 4 W


EMMET COUNTY

DESCRIPTION OF CORNER SECTION CORNER COMMON TO SECTIONS 25 - 26 - 35 - 36

CORNER MONUMENT SET 1" PIPE WITH 4" BRASS CAP

DATE MONUMENT PLACED AND WITNESSED MARCH 11, 1965

WITNESSES TO CORNER.....



6" CEDAR S40W 10.7

7" CEDAR N20E 11.5

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this township. Corner was set on line and midway between section corners 1 mile north and 1 mile south. No reliable corners west to effect a double proportionate restoration, although distance west to lake checks good.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE June 3, 1965
REGISTERED LAND SURVEYOR #10068