

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 39 N. R. 4 W


EMMET COUNTY

DESCRIPTION OF CORNER MEANDER CORNER COMMON TO SECTIONS ~~27-28~~<sup>26-27</sup> ON NORTH SIDE OF FRENCH FARM LAKE

CORNER MONUMENT SET 1/2" IRON BAR AND POST

DATE MONUMENT PLACED AND WITNESSED MARCH 12, 1965

WITNESSES TO CORNER.....



8" R. OAK N32W 10.1

10" R. PINE S56W 25.1

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS SET ON TRUE SECTION LINE AT NORTH SHORE OF LAKE ABOUT 20' FROM LAKE SHORE. FITS OLD MEANDER LINE NOTES GOOD. NO EVIDENCE OF ORIGINAL WITNESSES. A PINE IS LOCATED ABOUT 1.50 CHAINS EAST ON LAKE SHORE, BUT DO NOT BELIEVE IT SET RELATIVE TO OTHER RESTORED CORNERS IN THIS AREA.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE JUNE 3, 1965  
REGISTERED LAND SURVEYOR #10068