

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 39 N. R. 4 W


EMMET COUNTY

DESCRIPTION OF CORNER ½ CORNER COMMON TO SECTIONS 34 - 35

CORNER MONUMENT SET 1" PIPE WITH 4" ALUMINUM CAP

DATE MONUMENT PLACED AND WITNESSED MARCH 12, 1965

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" SPRUCE N82W 55.8'

4" SPRUCE S23W 18.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS SET BY PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNER SOUTH AND THEORETICAL POSITION FOR SECTION CORNERS IN LAKE. NO EVIDENCE OF PREVIOUS CORNER. FITS OKEY WITH N-S FENCE LINE ON S½ MILE OF THIS LINE.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE JUNE 3, 1965  
REGISTERED LAND SURVEYOR #10068