

SURVEY & REMONUMENTATION

DEED LIBER 2565 PAGE 891

APR 27 1995

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

GENESEE
(County)

Located In:

Corner Code =#

ARGENTINE TOWNSHIP

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>5N</u> R <u>5E</u> | <u>B-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

FEB 16 7 38 AM 1995

7801

REGISTER OF DEEDS

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RICHARD KRAFT, PS, in a field survey on OCTOBER 10, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1823/GLO HARVEY PARKE, D.S. SET POST, NO ACCESSORIES

PRO-TATIO OF GLO SURVEY
 S 1/4 COR. TO SE CORNER, 2657.82'
 S 1/4 COR. TO SW CORNER, 2620.86'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - RICHARD H. KRAFT, P.S. - FOUND 9" WOOD CORNER POST AT INTERSECTION OF EAST-WEST AND SOUTH FENCES
 MEASURED S 1/4 CORNER TO SE CORNER, 2656.58 FT.
 MEASURED S 1/4 CORNER TO SW CORNER, 2620.24 FT.

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Richard H. Kraft
 Date 12-21-94

RATIFIED BY GENESEE COUNTY PEER GROUP, DECEMBER 21, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 SET STANDARD GENESEE COUNTY MONUMENT
 N75°E, SET PK & GC TAG IN 12" ASH, 23.78'
 S1°W, SET PK & GC TAG IN WEST 12" TWIN 24" TREE, 12.45'
 S1°W, SET PK & GC TAG IN 36" OAK, 31.0'
 N85°W, SET PK & GC TAG IN 8" ASH, 27.80'



Signed by Richard H. Kraft Date DECEMBER 31, 1994
 Surveyor's Michigan License No. 10064