

SURVEY & REMONUMENTATION

MAR 23 2000

LAND CORNER RECORDATION CERTIFICATE Dec 21 2 46 PM '99
Filing Requirement of Act 74, Mich. P.A. 1970

Handwritten signature

SECTION

For corners in

Genesee Located In: Argentine Corner Code # E-4
(County)

GENESEE COUNTY
REGISTER OF DEEDS

MASTER LIBER 4355 PAGE 86

109070

filed & rec 900

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5N R 5E E-4
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Gibert G. Bonno, P.S., in a field survey on November 17 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1823, GLO - Harvey Parke, D.S., set wood post and two accessories, measured E-5 to E-4 and E-4 to E-3
- 1996, Certified survey - L.. 3473, P. 244-245 by Mark L. VanRaemdonck P.S. #24622, no description of monument given, no accessories given, measured E-4 to E-5
- 1996, Certified survey - L.. 3473, P. 246-248 by Mark L. VanRaemdonck P.S. #24622, no description given, no accessories given, measured E-4 to E-3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999 Remon - Found iron and cap #24622, 0.20 feet west of fence corner post, fence runs north and west.
- In the 1823 GLO survey by Harvey Parke, D.S. a wood post is indicated as the corner with two measurements, E-5 to E-4, 40 chains (2640 feet). In 1999 I measure 2676.07 feet, E-4 to E-3, 40 chains (2640 feet), 1999 I measure 2654.23 feet. In a 1996 Certified survey by Mark VanRaemdonck, RLS #24622 recorded on L. 3473, P. 244-245 with one measurement shown E-4 to E-5 of 2676.53 feet, (0.46 feet longer than 1999 measurement), and E-4 to E-3 of 2654.23 feet, (0.25 feet shorter than 1999 measurement).

Today in the 1999 remonumentation program I am finding an iron and cap #24622 (Mark L. VanRaemdonck) as the corner. I excavated down approximately three feet and found no remnants of previous monumentation. This corner falls in an area of old farm fields with little evidence of previous surveys. No County Surveyor records were found for this corner. I looked in the proportionate measure location and found no evidence indicating the corner should fall in a different location. I accept this corner as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- North 115.63' found iron and cap #24622
- N70°W 26.13' found spike and tag #24622 in S. face 10" twin Walnut
- West 25.27' Set spike and Genesee County Remonumentation tag in South face 36" 4' high stump
- S45°W 84.95' found iron and cap #24622
- Ratified by the Genesee County Peer Group 12-1-1999
- I set the Standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genesee County Remonumentation Corner 32332, 1999") with 30" x 2 3/8" O.D. stainless steel tube set in monument box.

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. *Carl Carlson*
Date 12-1-99



Signed by *Gilbert G. Bonno*
Surveyor's Michigan License No. 32332

Date 12/15/99