

SURVEY & REMONUMENTATION

MAR 23 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Handwritten signature
Dec 21 2 46 PM '99

SECTION

For corners in

Genesee Located In: Argentine Corner Code # G-4
(County)

GENESEE COUNTY
REGISTERED DEEDS
MASTER LIBER 4355 PAGE 83

109067

- 1. Public Land Survey T 5N R 5E G-4
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

filed & rec 900

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, Gilbert G. Bonno, P.S., in a field survey on November 17 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1823, GLO - Harvey Parke D.S., set wood post and two accessories, measured G-4 to G-3 and G-5 to G-4. Date unknown, McCollum Drain Description, no description of monument given, measures west to centerline of drain. 1992, LCRC, L. 2472 P. 666, A. Vance Kupisch P.S. # 13586, set "T" iron with cap #13586, four new accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 Remon - found "T" iron and cap # 13586 on top of east bank of McCollum Drain and four 1992 accessories, (South 22.91' N/T in W. face 8" Locust, East 24.71' N/T in N face 6" Oak, North 25.84' N/T in E face 8" tree, West 5.54' N/T in N face 8" Ash)

In 1823, the GLO survey by Harvey Parke, D.S. indicated a wood post was set as the corner, with two measurements G-3 to G-4, 40 chains (2640 feet); I measure 2649.17 feet in 1999 and G-4 to G-5, 40 chains (2640 feet); I measure 2653.01 in 1999. Two accessories were listed, neither of which exists today. In the final determination of McCollum Drain, date unknown, one measurement west 0.15 chains (9.9 feet) is listed. I measure west 12.0 feet in 1999. Four accessories are noted on the 1992 P.A. 74 by Vance Kupisch, all four were found in the 1999 remonumentation program and compare within 0.01 to 0.09 feet of record. No measurements between Section corners are indicated on said 1972 P.A. 74. In the 1999 remonumentation program I am finding a "T" iron with cap # 13586 as the corner. I excavated further down three plus feet and found no remnants of any other object. I found remnants of a fence running west, north and east. This corner is in an area of old farm fields with little division of property taking place. I found no record of County Surveyor activity for this corner. I accept this found "T" iron as the best available evidence of the original position of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 23.00' Found N/T # 13586 in W. face 8" Locust
East 24.74' Found N/T #13586 in N. face 6" Oak
North 25.84' Found N/T #13586 in E. face tree
West 5.49' Found N/T #13586 in N. face 8" Ash

Ratified by the Genesee County Peer Group
12 - 1, 1999
I set the Standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genesee County Remonumentation Corner 32332, 1999") with 30" x 2 3/8" O.D. stainless steel tube set in monument box.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. *Paul Carter*
Date 12-1-99



Signed by *Gilbert G. Bonno*
Surveyor's Michigan License No. 32332

Date 12/15/99