

MAR 23 2000

SECTION



AND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 2 45 PM '99

For corners in

Genesee

Located In: Argentine Corner Code # K-2

(County)

GENESEE COUNTY
REGISTER OF DEEDS

MASTER LIBER 4355 PAGE 84

109068

filed & rec 9:00
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5N R 5E K-2
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Gilbert G. Bonno, P.S., in a field survey on November 17 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823, GLO Harvey Parke DS, set wood post and two accessories
- 1874, County Survey Records - Billings CS, stake and stone, no new accessories, measured between K-2 and K-1, and K-2 and J-2
- 1895, County Survey Records - George W. Doane CS, stone, no new accessories
- No Date, Updated minutes of the Survey of the Porter drain, measured east and south to Section lines.
- 1974, Certified Survey & LCRC, L. 1907, P. 464,475, by Marvin D. Pike #11166; three new accessories, measured between K-2 and K-1.
- 1978, ROWE witness card, plow point, three new accessories.
- 1997, FSE witness, "T" iron, four new accessories, measured between K-2 and K-3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 - Found a "T" iron and three accessories from 1997 (North 22.33' to found K.R. Carlson nail/tag in west face 12" Walnut, S25°E 56.67' to found PK/Carlson tag at east end of 12" CMP, S50°W 43.85' to found nail/flagging in east face wood post)

In the 1823 survey by Harvey Parke, DS, a wood wood post is indicated as the corner, with a measurement shown, K-2 to K-1 of 44.70 chains (2950.20 feet). The 1874 Genesee County Survey Records, Small book-Narrative Record, Page 174 by S.R. Billings indicates two measurements, K-2 to K-1 = 45.02 chains (2671.32 feet) and K-2 to J-2 = 39.77 chains (2624.82 feet) or 39.76 chains (2624.16 feet), K-2 is described in 1974 witness card K-2 is described as a stone by C.S. George W. Doane. From a 1978 ROWE witness card K-2 is described as a plow point, with four accessories listed. None of which exist today. A 1974 Certified Survey by Marvin D. Pike P.S. #11166 showed a distance measured K-2 to K-1=2950.20 feet, however no description of the monument is given. In a 1997 sketch with corner witnesses from Flint Surveying and Engineering, a "T" iron is described as the corner. Their measurement from K-2 to K-3 =2566.68 feet.

Today in the 1999 remonumentation program I am finding a "T" iron at the centerline-centerline of Morrish and Whitney Roads Below the "T" iron I found a plow point surrounded by rocks. The plow point was 0.63 feet north and 0.25 feet east of the "T" iron. Below the plow point I found remnants of a cedar post in the center of an 8" steel casing. The remnants of the wood post were 0.71 feet north and 0.06 feet east of the "T" iron. Based on the history of this corner I accept the position of the wood remnants in steel casing as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- N10°E 22.83' to found double head nail in West face wood post
- North 22.33' to found K.R. Carlson nail/tag in west face 12" Walnut
- S25°E 56.67' to found pk/tag at east end 12" CMP
- S30°W 44.29' to found mag nail in east face 12" Pine
- S50°W 44.05' to found mag nail NNW face wood post
- S50°W 43.85' to found nail/flagging in east face wood post
- N20°W 39.48' to found mag nail/flagging in ENE face 10" Hickory

I set the Standard Bernsten Monument
SS-A-5-BR-30 (3 1/4" D. Brass cap
Stamped "Genesee County Remonumentation
Corner 32332, 1999") with 30" x 2 3/8" O.D.
Stainless Steel tube with plastic base.

Ratified by the Genesee County Peer Group
November 17, 1999.

Signed by Gilbert G. Bonno
Surveyor's Michigan License No. #32332

Ratified by Peer Group on 12/15/99
in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson