

**1998 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4013 PAGE 120

For corners in

Genesee County Located In: Corner Code #

- 1. Public Land Survey T5N R6E A-2
- 2. Property Controlling in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

SURVEY &
REMONUMENTATION

106848

MAR 17 1999

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____ SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Kevin B. Cleaver, in a field survey on November 19, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This closing corner was not established in the original government survey of T5N-R6E. May 1823 General Land Office (GLO) fieldnotes for corner M-2, T5N-R5E: set post w/two accessories 5-18-1995 GEI survey in NW fractional 1/4 Section 6, T5N-R6E: 5-13-1996 Tax Roll Description for parcel 25-06-100-003

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
Recovered iron from tax roll description and, working backwards, re-established the position for setting the quarter corner

The method for setting this corner was ratified by the Genesee County Remonumentation Peer Review Committee on November 18, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" in center of rock pile at old wooden anchor post

- NORTH 75.60' set nail/tag in W face 12" ash
- NORTH 192.23' set nail/tag in W face 12" ash
- EAST 21.71' set nail/tag in S face 10" tree
- EAST 328.26' set nail/tag in S face 6" hickory

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson
Date 11-18-98

GENESEE COUNTY REGISTER OF DEEDS
DEC 11 10 54 AM '98
Mark P. Kelly

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S.
Surveyor's Michigan License No. 29242



Date 12/8/98