

**1998 GENESEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Genesee County

Located In:

Corner Code #

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

T5N R6E  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

A-4

**SURVEY &  
REMONUMENTATION**

MAR 17 1999

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

SECTION \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on November 19, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This closing corner was not established in the original government survey of T5N-R6E. May 1823 General Land Office (GLO) fieldnotes for corner M-4, T5N-R5E: set post w/two accessories 5-13-1996 Tax Roll Descriptions for parcels 25-06-07-100-001 and 25-06-07-300-002

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found  
Recovered irons in each of the tax roll descriptions and, working backwards, re-established the position setting the quarter corner

The method for setting this corner was ratified by the Genesee County Remonumentation Peer Review Committee on November 18, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" approximately 4" above grade

- N 70° W 31.69' set nail/tag in N face 15" hickory
- S 60° W 38.53' set nail/tag in NW face 18" oak
- S 10° E 42.59' set nail/tag in W face 12" ash
- NORTH 49.45' set nail/tag in E face 48" oak

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson  
Date 11-18-98

Signed by Kevin Banfield Cleaver  
Kevin Banfield Cleaver, P.S.

Surveyor's Michigan License No. 29242



Date 12/8/98

MASTER LIBER 4013 PAGE 119

106847

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

GENESEE COUNTY REGISTER OF DEEDS

DEC 11 1998

*Kevin Banfield Cleaver*