

**1998 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER **4013** PAGE **117**

For corners in

<u>Genesee County</u>	Located In:	Corner Code #
1. Public Land Survey	T5N R6E	B-5
2. Property Controlling in Section	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		SECTION _____
5. Private Claims _____		_____

SURVEY &
REMONUMENTATION

MAR 17 1999

106845

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10					12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

I, Kevin B. Cleaver, in a field survey on November 5, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4-15-1823, General Land Office (GLO) fieldnotes: set post w/two accessories
 1965 Gould Engineering, Inc. (GEI) records: iron w/four accessories
 9-15-1989 Land Corner Recordation Certificate (LCRC) Liber 2380, Page 998: 1/2" rered in monument box w/three accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
 Corner and accessories from 1965 GEI records not found
 Recovered corner and accessories as identified in 1989 LCRC

The monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 4, 1989

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" in monument box over 1/2" rered.

North 50.19' chiseled "x" in top of ROW marker
 SOUTH 49.35' chiseled "x" in top of ROW marker
 N 50° E 66.25' nail/tag #32332 in 5th fence post east of wood plank fence
 N 45° W 72.15' southeast bolt of old signon cylindrical concrete base

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl Carlson
 Date 11-4-98

GENESEE COUNTY
REGISTER OF DEEDS
DEC 11 10 54 AM '98
Kevin B. Cleaver

Signed by Kevin Banfield Cleaver
 Kevin Banfield Cleaver, P.S.



Date 12/3/98

Surveyor's Michigan License No. 29242

DGR/bb
 98-GCRM-DGR-2796