

1998 GENESEE COUNTY REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASTER LIBER 4013 PAGE 115

Genesee County Located In: Corner Code #

1. Public Land Survey T5N R6E C-4
 2. Property Controlling S T R SURVEY & RECORDATION
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R MAR 17 1999

106843

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7	8			9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kevin B. Cleaver, in a field survey on November 24, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4-15-1823 General Land Office (GLO) fieldnotes: set post w/two accessories
 5-13-1996 Tax Roll Description for parcel 25-06-07-200-017

GENESEE COUNTY REGISTER OF DEEDS
 DEC 11 10 54 AM '98
Kevin B. Cleaver

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
 Recovered three irons as defined in tax roll description and, working backwards, re-established the position for setting the quarter corner
 The method for setting this corner was ratified by the Genesee County Remonumentation Peer Review Committee on November 18, 1989


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" approximately 4" above grade with rock piled on top

N 30° W 71.80' set nail/tag in SW face twin 18" maple
 N 20° E 24.24' set nail/tag in SE face 13" oak
 N 40° E 49.74' set nail/tag in NW face 27" maple
 S 60° E 27.64' set nail/tag in N face 27" hickory
 WEST 1.4' north-south running wire fence

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl Carlson
 Date 11-18-98

Signed by Kevin Banfield Cleaver
 Kevin Banfield Cleaver, P.S.
 Surveyor's Michigan License No. 29242



Date 12/8/98