

**1998 GENESEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4013 PAGE 114

For corners in

Genesee County Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T5N R6E C-5 \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**106842**

**SURVEY &  
REMONUMENTATION**

Register of Deeds Stamp & File Number

MAR 17 1999

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

SECTION

I, Kevin B. Cleaver, in a field survey on November 5, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3					1
3													
4		7		8		9		10		1			12
5													
6		18		17		16		15		1			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		2			25
11													
12		31		32		33		34					36
13													

A. Description of original monument and accessories and/or subsequent restoration:

4-15-1823 General Land Office (GLO) fieldnotes: set post w/two accessories  
 Undated Gould Engineering, Inc. (GEI) records: corner unidentified w/three accessories  
 4-4-1953 Recorded plat of "Curtwood Manor" dimensioned to C-5  
 1965 GEI records: corner unidentified w/three accessories  
 Undated GEI records: corner unidentified w/four accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found  
 Recovered one accessory from undated GEI records  
 Checked dimension to "Curtwood Manor"  
 Recovered two accessories from 1965 GEI records  
 Recovered one accessory from undated GEI records

The monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 4, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" over 1/2" rerod in monument box

N 08° E 47.47' set Genesee County Witness tag in east face 20" oak  
 N 50° E 72.19' set Genesee County Witness tag in southeast face 6" fence post  
 SOUTH 50.30' found PK Nail/brass washer in east face power pole  
 N 32° W 62.33' set Genesee County Witness tag in northeast face 36" willow

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Paul Carlson  
 Date 11-4-98

Signed by Kevin Banfield Cleaver  
 Kevin Banfield Cleaver, P.S.  
 Surveyor's Michigan License No. 29242



Date 12/2/98

REGISTER OF DEEDS  
 DEC 11 10 59 AM '98  
*McL...*