

1998 GENESEE COUNTY REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MASTER LIBER 4013 PAGE 110

For corners in

Genesee County Located In: Corner Code #

1. Public Land Survey T5N R6E E-4
 2. Property Controlling S T R SURVEY & RE-MONUMENTATION
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 MAR 17 1999

106838

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____ SECTION _____

I, Kevin B. Cleaver, in a field survey on November 5, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

A. Description of original monument and accessories and/or subsequent restoration:

4-15-1823 General Land Office (GLO) fieldnotes: set post w/two accessories
 4-30-1990 PA 132 Certified Survey, Liber 2392, Page 160: iron/cap w/four accessories
 8-28-1990 Land Corner Recordation Certificate (LCRC), Liber 2415, Page 44: iron/cap w/four accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
 Recovered corner and three accessories from 1990 PA 132 survey
 Recovered corner and three accessories from 1990 LCRC

The monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 4, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" over 1/2" rered with cap #14093

N 50° E 22.19' found nail/tag #14093 in northwest face 12" elm
 S 50° E 58.06' set Genesee County Witness tag in southwest face 7" ash
 SOUTH 39.18' set Genesee County Witness tag in west face 12" oak
 N 10° W 26.77' set Genesee County Witness tag in west face 6" poplar

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Larson
 Date 11-4-98

Signed by Kevin Banfield Cleaver
 Kevin Banfield Cleaver, P.S.

Surveyor's Michigan License No. 29242

DGR/bb
 98-GCRM-DGR-2798



Date 12/8/98

GENESEE COUNTY REGISTER OF DEEDS
 DEC 11 10 54 AM '98
McL...