

**1998 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Genesee County Located In: _____ Corner Code # _____

1. Public Land Survey T5N R6E K-2
 2. Property Controlling S _____ T _____ R _____ SURVEY &
 in Section S _____ T _____ R _____ REMONUMENTATION
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____ MAR 17 1999

MASTER LIBER 4013 PAGE 99

106827

Register of Deeds Stamp # File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on November 5, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

4-15-1823 General Land Office (GLO) fieldnotes: set post w/two accessories
 Undated Gould Engineering, Inc. (GEI) records: stone, iron, w/five accessories
 11-16-1981 Land Corner Recordation Certificate (LCRC), Liber 2126, Page 378: rod in monument box w/four accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
 Recovered iron only from undated GEI records
 Recovered corner as identified and two accessories from 1981 LCRC

The monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 4, 1998

GENESEE COUNTY REGISTER OF DEEDS
 DEC 11 10 53 AM '98
Michael J. McLean

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" over 1/2" rerod in monument box.

NORTH 53.38' found MSHD nail/tag in east face power pole
 S 23° E 59.00' set Genesee County Witness tag in west face power pole
 S 15° W 59.02' set Genesee County Witness tag in west face power pole
 S 53° W 71.25' set Genesee County Witness tag in southwest face 14" tree
 SOUTH 3.5' painted centerline of Thompson Road

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Larson
 Date 11-4-98

Signed by Kevin Banfield Cleaver
 Kevin Banfield Cleaver, P.S.

Surveyor's Michigan License No. 29242

DGR/bb
 98-GCRM-DGR-2803



Date 12/8/98