

MAY 2 1997

COMPL.

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T 6N R 5E	C-4
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

DEC 19 10 16 AM '96

RECORDED
REGISTERED

81559

Register of Deeds Stamp & File Number

900
filed
to file

I, Kevin B. Cleaver, P.S., in a field survey on June 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

May, 1823, GLO	Set post, no accessories
June 20, 1968	Recorded plat of "Duffield Meadows", plat mons.
Oct., 13, 1982	Survey by Elbex Harris, P.S. #9431
April 26, 1994	Certified survey, Liber 2543, Pages 86-88; RRS in pavement, with six (6) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date Jan 3, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike in pavement, fits the found monumentation of the 1968 plat of "Duffield Meadows"; found six(6) of the accessories from 1994 survey Liber 2543, Pages 86-88.

The monument found was ratified by the Genesee County Peer Review Committee on January 3, 1996. This monument is to be set with the 1996 remonumentation corners due to the existing frost conditions.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County Remonumentation Corner 1995; #29242 over a railroad spike in pavement.

N 85° E	26.62'	Found top center west edge I-beam post
S 60° W	25.45'	Found top center east edge I-beam post
S 60° E	31.10'	Found top center west edge I-beam post
N 65° W	23.36'	Found top center east edge I-beam post

NOTE: This monument is six (6) inches in length due to an existing CMP running under the road.

Signed by Kevin Banfield Cleaver, P.S.
Surveyor's Michigan License No. 29242



Date JUNE 14, 1996