100

BAY 2 0 1997

SOUTH SENCE


1996	REMONUMENTATION	PROGRAM!
LAND COF	RNER RECORDATION	CERTIFICATE

LAND	CONNER	RECU	NUA	HUI	NOCH	11151	المجاب	_
							1	
P**********	Requirem		A -4	74	Mich	DA	107	۸
riiina	Requirem	eni oi	MUL	14.	IVIICII.	Г.М.	131	v

Fo	r corners in	riing Require	Filing Requirement of Act 74, Wich. F.A. 1970		
(Genesee County	Located In:	Corner Code ##		
1.	Public Land Survey	T 6N R 5E	C-5		
		T B	v		
		T R T R		S C	
2.	Property Controlling	S RR		04550	
	in Section	S R		8155 8	
3.	Miscellaneous	S T R		Register of Deeds Stamp & File Number	
	Property in Sec.	S R		- 	
4.	Lot No	, Recorded Plat		A B C D E F G H I J K	
5.	Private Claims				
			• (3	

_____, 19 __96 Kevin B. Cleaver, P.S., in a field survey on __June_3_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United Stales Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



Set post with two (2) accessories May 22, 1983, GLO L.C.R.C., Liber 1899, Page 7, found steel bar, with July 17, 1974 three (3) accessories Survey by PS #9431, found 1" square bar with October 13, 1982 three (3) accessories from 1974, L.C.R.C. April 28, 1994

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Certified survey, Liber 2543, Pages 86-88, found 1" hex bar, with one (1) 1974 and 1982 accessory, with four (4)

new accessories

Ratified by Peer Grou accordance with P.A. 345,

Co. Reb.

Date ()

Found 1" square iron bar; found four (4) accessories from 1974 L.C.R.C.; found three (3) accessories from 1982 survey; found five (5) accessories from 1994 certified survey.

The monument found was ratified by the Genesee County Peer Review Committee on January 3, 1996. This monument is to be set during the 1996 program, due to the existing frost conditions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set in concrete the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped

Genesee County Remonumentation Corner 1995, #29242 over found 1" square iron bar. Northwest corner of church S 45° E 94.80

KEVIN

N 45° E Nail/washer #10057 in southeast face of power pole 36.16' North edge of stop sign post S 75° W 52.25' South face of 2" steel fence post N 65° W 43.30 East face of 2 steel lefter post N 25° W 50.50

NFIELD CLEAVER Kevin Banfield Cleaver, P.S., Surveyor's Michigan License No.

LINE 3, 19960 Date-