

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM, LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee

(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 6N R 5E D-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECORDED REGISTERED DEC 19 10 14 AM '96 81561 Register of Deeds Stamp & File Number

I, Kevin B. Cleaver, P.S., in a field survey on June 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- May, 1823, GLO Set post with two (2) accessories
July 17, 1974 L.C.R.C., Liber 1899, Page 7, found railroad spike, with three (3) accessories
Dec., 6, 1983 Certified survey, Liber 2181, Pages 315 and 316, found railroad spike, with four (4) accessories
Jan., 25, 1994 Certified survey, Liber 2525, Pages 678 and 679, re-rod and cap #24622, with four (4) accessories
April 26, 1994 Certified survey, Liber 2543, Pages 86, 87 and 88, re-rod and cap #24622, with four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in gravel, found two (2) accessories from L.C.R.C., Liber 1899, Page 7; found four (4) accessories from certified survey, Liber 2181, Pages 315 and 316; found one (1) new accessory from certified survey, Liber 2525, Pages 678 and 679.

The monument found was ratified by the Genesee County Peer Review Committee on January 3, 1996, as the accepted corner. This monument is to be set with the 1996 Remonumentation Corners due to the existing frost conditions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County Remonumentation Corner 1995, #29242 over a 1/2" re-rod in gravel road.

- S 07° W 26.42' Found PK/disk in west face of telephone pole
N 10° E 56.56' Found PK/flagging in east face of power pole
S 66° E 89.75' Set Genesee County Remonumentation Tag in southwest face of 8" tree
S 63° W 48.25' Set Genesee County Remonumentation Tag in southeast face of 9" tree

Grid table with columns A-M and rows 2-13. A dot is marked at row 5, column C.

Ratified by Peer Group in accordance with P.A. 945, 1996

Co. Rep. Carl [Signature] Date Jun 3, 1996

Signed by Kevin Banfield Cleaver, P.S., Its Field Manager

Date JUNE 3, 1996

Surveyor's Michigan License No. 29242

