

MAY 20 1997

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
REGISTERED
DEC 19 10 14 AM '96
GENESEE COUNTY REGISTER

For corners in

Genesee <small>(County)</small>	Located In:	Corner Code -#
1. Public Land Survey	T 6N R 5E	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

81556

Register of Deeds Stamp & File Number

g.p. filed in file

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Kevin B. Cleaver, P.S., in a field survey on June 7, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

May 1823, GLO 1994 Set post with two (2) accessories Records from E.E. Anderson PS #11495, found 1 1/2" pipe with four (4) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl [Signature]
Date Jan 3, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1 1/2" pipe; this monument fits four (4) accessories from 1994 records by P.S. #11495.

The monument found was ratified by the Genesee County Peer Review Committee on January 3, 1996. The new monument is to be set with the 1996 remonumentation program due to existing frost conditions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County Remonumentation Corner 1995, #29242, over a 1 1/2" pipe.

South	46.38'	Inside gauge of north rail of railroad tracks
North	36.15'	Found railroad spike in southeast face of 48" oak
N 05° E	6.15'	Found nail/alpha tag in west face of fence post
S 70° W	52.11'	Found nail/alpha tag in south face of fence post
East	60.38'	Found nail/alpha tag in north face of telephone pole

Signed by Kevin Banfield Cleaver
Surveyor's Michigan License No. 29242



JUNE 7, 1996