

MAY 20 1997

COMMISSION

MASTER LIBER 3432 PAGE 146

1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee (County) Located In: Corner Code: #/

1. Public Land Survey	T 6N R 5E	G-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED  
DEC 19 10 14 AM '96

RECORDED

81553

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, P.S., in a field survey on June 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

May 26, 1823, GLO Set post, with two (2) accessories  
 Feb. 2, 1973 L.C.R.C., Liber 1977, Page 788, 'T' iron, with three (3) accessories  
 April 23, 1973 Certified survey, Liber 1897, Page 347, found 'T' bar, with four (4) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson  
Date Jan 3, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' iron in gravel road; we found two (2) of the accessories from the 1973 L.C.R.C.; we also found three (3) of the accessories from the 1973 certified survey.

The monument found was ratified by the Genesee County Peer Review Committee on January 3, 1996, as the accepted corner. This monument is to be set with the 1996 remonumentation corners due to frost conditions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County Remonumentation Corner 1995, #29242 over a 'T' iron in gravel road.

East	31.98'	Found Carlson tag in the south face of power pole
West	40.20'	Set Genesee County remon. tag in the south face of 10" ash
N 25° W	48.28'	Set Genesee County remon. tag in the northeast face of multi-stem maple
N 75° E	56.43'	Set Genesee County remon. tag in the southeast face of 12" ash

Signed by Kevin Banfield Cleaver  
Surveyor's Michigan License No. 29242



Date JUNE 3, 1996