

SURVEY & REMONUMENTATION

MAY 31 2000

1995 REMONUMENTATION PROGRAM

SECTION

MASTER LIBER 3276 PAGE 434

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GENESEE

(County)

Located In: MUNDY

Corner Code: C-5

- 1. Public Land Survey T 6N R 6E C-5
- T R
- T R
- T R
- 2. Property Controlling S T R
- In Section S T R
- 3. Miscellaneous S T R
- Property In Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

20111

RECORDED
REGISTERED
APR 4 2 56 PM '95

9.00 Filed + Recd

Register of Deeds Stamp & File Number

I, RICHARD H. KRAFT, In a field survey on DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO --HARVEY PARKE, DEPUTY SURVEYOR - SET CORNER - NO ACCESSORIES
- 1885 - F.W. PETTEE, COUNTY SURVEYOR - FOUND OAK STAKE & BRICKS - 2 ACCESSORIES
- GCRC - FOUND STAKE - 3 ACCESSORIES
- 1971 - A.F. MILLER - FOUND "T" BAR - 3 ACCESSORIES
- 1976 - K. PIOTROWSKI - FOUND "T" IRON - 3 ACCESSORIES
- 1995 - RICHARD H. KRAFT - FOUND "T" IRON IN MONUMENT BOX

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 GENESEE COUNTY REMONUMENTATION PROGRAM

- 1971 - FOUND THREE ACCESSORIES
- 1976 - FOUND TWO ACCESSORIES

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Calm
Date 12-20-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD GENESEE COUNTY MONUMENTS IN MONUMENT BOX
- ROAD SIGN - S45°E, 47.25 FT.
- GC TAG IN POWER POLE, S45°W, 79.85 FT.
- ROAD SIGN - N45°W, 41.32 FT.
- W END MANHOLE RIM N50°E, 51.73 FT.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

Signed by Richard H. Kraft
Surveyor's Michigan License No. 10064

Date 12-22-95

