

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GENESEE

(County)

Located In:

Corner Code =//

- 1. Public Land Survey      T 6N R 6E      G-5
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Sec.         S    T    R

RECORDED  
APR 4 2 55 PM '95  
FILED  
20117  
9.00  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, RICHARD H. KRAFT, in a field survey on DECEMBER, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0		5		4		9		2				
3													
4	7		8		9		10		11		12		
5							15		14		13		
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	01		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 - GLO - HARVEY PARKE, DEPUTY SURVEYOR - SET CORNERS - NO ACCESSORIES
- 1920 - GENESEE COUNTY ROAD COMMISSION FOUND STONES & BRICKS - 3 ACCESSORIES
- 1972 - M.F. FOUTZ - FOUND 1" BAR IN MONUMENT BOX - 4 ACCESSORIES
- 1995 - R.H. KRAFT - FOUND 1" ROD IN MONUMENT BOX

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 GENESEE COUNTY REMONUMENTATION PROGRAM

- 1972 - 1" BAR IN MONUMENT BOX - FOUND BY M.F. FOUTZ
- 1995 - FOUND IRON ROD IN MONUMENT BOX - FOUND 3 - 1972 ACCESSORIES

Handled by Peer Group in accordance with P.A. 345, 1990  
Co. Rep. Carl Carlson  
Date 12-20-95

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

- SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
- NAIL & TAG IN POWER POLE - N40°E, 69.90 FT.
- NW CORNER PORCH (#7007) S45°E, 72.36 FT.
- NAIL & TAG IN POWER POLE, S45°W, 42.55 FT.
- CENTERLINE PAVEMENT, WEST 2.0 FT.
- NAIL & TAG IN 14" WALNUT, S25°W, 111.90 FT.

SURVEY & REMONUMENTATION

MAY 31 2000

SECTION 

Signed by Richard H. Kraft  
Surveyor's Michigan License No. 10064

Date 12-23-95

010