

RECORDED
REGISTER OF DEEDS
APR 4 2 56 PM '95

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GENESEE

(County)

Located In:

Corner Code H-5

1. Public Land Survey

T 6N R 6E

H-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

20118

9.00 Filed & Recd

Register of Deeds Stamp & File Number

I, RICHARD H. KRAFT, in a field survey on DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed, below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 - GLO-HARVEY PARKE, DEPUTY SURVEYOR - SET CORNER - NO ACCESSORIES
- 1920 - GCRC - CENTER OF 2 TON STONE - 4 ACCESSORIES
- 1980 - P. PANGRES - FOUND "T" IRON - 4 ACCESSORIES
- 1995 - K. B. CLEAVER - FOUND "T" IRON - 4 ACCESSORIES
- 1995 - RICHARD H. KRAFT - FOUND "T" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 GENESEE COUNTY RE-MONUMENTATION PROGRAM

- 1980 - FOUND 2 ACCESSORIES
- 1995 - FOUND 3 ACCESSORIES
- 1995 - FOUND "T" IRON

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson
Date 12-20-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
- SET GC TAG IN 4" TREE, N 45°W, 27.65 FT.
- FOUND NAIL & TAG IN 18" WALNUT - S 70° W, 58.11 FT.
- FOUND NAIL & TAG IN 15" PINE - S 65° E, 66.2 FT.
- FOUND NAIL & TAG IN 24" MAPLE - N 60° W, 85.95 FT.
- SET GC TAG IN 16" TREE - SOUTH 30.1 FT.

SURVEY & REMONUMENTATION

MAY 31 2000

SECTION

Signed by Richard H. Kraft
Surveyor's Michigan License No. 10064

Date 12-23-95

87